

PH	CODE	DESCRIPTION	QTY	UNIT	FLR
BAS	D.3.3	Bridging/blocking L3	631.2	LF	L3
BAS	D.4.1	Floor joists/trusses L4 @16" o.c.	7890.0	LF	L4
BAS	D.4.2	Rim/band L4	420.0	LF	L4
BAS	D.4.3	Bridging/blocking L4	631.2	LF	L4
BAS	D.5.1	Floor joists/trusses L5 @16" o.c.	7890.0	LF	L5
BAS	D.5.2	Rim/band L5	420.0	LF	L5
BAS	D.5.3	Bridging/blocking L5	631.2	LF	L5
BAS	D.ALT	Floor joists ALT @24" o.c. (all L2-L5)	21040.0	LF	L2-L5
BAS	E.1	Roof joists/trusses @24" o.c.	5500.0	LF	ROOF
BAS	E.2	Roof rim/edge	420.0	LF	ROOF
BAS	E.3	Roof framing area	11000.0	SF	ROOF
BAS	G.1	Hold-downs / straps / clips / screws	1	LS	ALL
BAS	G.2	160 mph continuous load path hardware	1	LS	ALL
BAS	H.1	Delivery to Harvey LA 70058	1	LS	ALL
ALT	B.2.1	Corridor+demising studs L2	652.5	PCS-EQ	L2
ALT	B.2.2	Corridor+demising track L2	1740.0	LF	L2
ALT	B.3.1	Corridor+demising studs L3	652.5	PCS-EQ	L3
ALT	B.3.2	Corridor+demising track L3	1740.0	LF	L3
ALT	B.4.1	Corridor+demising studs L4	652.5	PCS-EQ	L4
ALT	B.4.2	Corridor+demising track L4	1740.0	LF	L4
ALT	B.5.1	Corridor+demising studs L5	652.5	PCS-EQ	L5
ALT	B.5.2	Corridor+demising track L5	1740.0	LF	L5
ALT	B.L1	L1 Mirage CRAVE demising + BOH allow s	2101.9	LF	L1
ALT	B.L1t	L1 interior track	380.0	LF	L1
ALT	F.1	Insulated wall panels or sheathing NET	24878.0	SF	ALL
ALT	F.2	Roof deck/panels	11000.0	SF	ROOF
ALT	F.3	Erection labor + crane	1	LS	ALL

CD DRAFT for bidding & AOR/PE completion. Geometry & TAKEOFF-4 quantities locked. Member sizes, sealed calcs, shop drawings by licensed professionals.

MIRAGE @ MANHATTAN

1705 Manhattan Blvd · Harvey LA 70058 · Jefferson Parish

STRUCTURAL SCHEDULES — TAKEOFF CONT. + ALT

SHEET S5.1

SCALE: N/A

CD-DRAFT-2 · FULL BUILD-OUT · JUL 15, 2026

OWNER-GC CD DRAFT · NOT SEALED

AOR / PE SEAL

(blank — Louisiana license)